

NORTHWESTERN UNIVERSITY
PROJECT NAME _____
JOB # _____

FOR: _____
ISSUED: 03/29/2017

SECTION 08 4113 - ALUMINUM-FRAMED ENTRANCES AND STOREFRONTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:

1. Exterior and interior storefront framing.
2. Storefront framing for window walls.
3. Storefront framing for ribbon walls.
4. Storefront framing for punched openings.
5. Exterior and interior manual-swing entrance doors and door-frame units.

1.3 ACTION SUBMITTALS

- A.

NORTHWESTERN UNIVERSITY

PROJECT NAME _____

JOB # _____

FOR: _____

ISSUED: 03/29/2017

- D. Samples for Initial Selection: For units with factory-applied color finishes.
- E. Samples for Verification: For each type of exposed finish required, in manufacturer's standard

NORTHWESTERN UNIVERSITY

PROJECT NAME _____

JOB # _____

FOR: _____

ISSUED: 03/29/2017

- B. Maintenance Data for Structural Sealant: For structural-sealant-glazed storefront to include in maintenance manuals. Include ASTM C

- a. Operable Units: Provide a minimum 1/16-inch (1.6-mm) clearance between framing members and operable units.
2. Cantilever Deflection: Where framing members overhang an anchor point, as follows:
 - a. Perpendicular to Plane of Wall: No greater than 1/240 of clear span plus 1/4 inch (6.35 mm) for spans greater than 11 feet 8-1/4 inches (3.6 m) or 1/175 times span, for spans less than 11 feet 8-1/4 inches (3.6 m).
- E. Structural: Test according to ASTM E 330 as follows:
 1. When tested at positive and negative wind-load design pressures, assemblies do not evidence deflection exceeding specified limits.
 2. When tested at 150 percent of positive and negative wind-load design pressures, assemblies, including anchorage, do not evidence material failures, structural distress, or permanent deformation of main framing members exceeding 0.2 percent of span.
 3. Test Durations: As required by design wind velocity, but not less than 10 seconds.
- F. Air Infiltration: Test according to ASTM E 283 for infiltration as follows:
 1. Fixed Framing and Glass Area:
 - a. Maximum air leakage of 0.06 cfm/sq. ft. (0.30 L/s per sq. m) at a static-air-pressure differential of 6.24 lbf/sq. ft. (300 Pa).
 2. Entrance Doors:
 - a. Pair of Doors: Maximum air leakage of 1.0 cfm/sq. ft. (5.08 L/s per sq. m) at a static-air-pressure differential of 1.57 lbf/sq. ft. (75 Pa).
 - b. Single Doors: Maximum air leakage of 0.5 cfm/sq. ft. (2.54 L/s per sq. m) at a static-air-pressure differential of 1.57 lbf/sq. ft. (75 Pa).
- G. Water Penetration under Static Pressure: Test according to ASTM E 331 as follows:
 1. No evidence of water penetration through fixed glazing and framing areas when tested according to a minimum static-air-pressure differential of 20 percent of positive wind-load design pressure, but not less than 6.24 lbf/sq. ft. (300 Pa).
- H. Interstory Drift: Accommodate design displacement of adjacent stories indicated.
 1. Design Displacement: **<Insert design displacement>**.
 2. Test Performance: Complying with criteria for passing based on building occupancy type when tested according to AAMA 501.4 at design displacement and 1.5 times the design displacement.
- I. Seismic Performance: Aluminum-framed entrances and storefronts shall withstand the effects of earthquake motions determined according to ASCE/SEI 7.
 1. Seismic Drift Causing Glass Fallout: Complying with criteria for passing based on building occupancy type when tested according to AAMA 501.6 at design displacement and 1.5 times the design displacement.
 2. Vertical Interstory Movement: Complying with criteria for passing based on building occupancy type when tested according to AAMA 501.7 at design displacement and 1.5 times the design displacement.

NORTHWESTERN UNIVERSITY

PROJECT NAME _____

JOB # _____

FOR: _____

ISSUED: 03/29/2017

J. Energy Performance: Certify and label energy performance according to NFRC as follows:

1. Thermal Transmittance (U-factor): Fixed glazing and framing areas shall have U-factor of not more than 0.69 Btu/sq. ft. x h x deg F (3.92 W/sq0.s:

NORTHWESTERN UNIVERSITY

PROJECT NAME _____

JOB # _____

FOR: _____

ISSUED: 03/29/2017

3. Glazing Plane: <Insert location>.
 4. Finish: [**Clear anodic finish**] [**Color anodic finish**] [**High-performance organic finish**].
 5. Fabrication Method: Field-fabricated stick system.
- B. Backer Plates: Manufacturer's standard, continuous backer plates for framing members, if not

- B. General: Provide entrance door hardware and entrance door hardware sets indicated in "Entrance Door Hardware Sets" Article for each entrance door to comply with requirements in this Section.
1. Entrance Door Hardware Sets: Provide quantity, item, size, finish or color indicated, and products equivalent in function and comparable in quality to named products.
 2. Sequence of Operation: Provide electrified door hardware function, sequence of operation, and interface with other building control systems indicated.
 3. Opening-Force Requirements:
 - a. Egress Doors: Not more than 15 lbf (67 N) to release the latch and not more than 30 lbf (133 N) to set the door in motion and not more than 15 lbf (67 N) to open the door to its minimum required width.
 - b. Accessible Interior Doors: Not more than 5 lbf (22.2 N) to fully open door.
- C. Designations: Requirements for design, grade, function, finish, size, and other distinctive qualities of each type of entrance door hardware are indicated in "Entrance Door Hardware Sets" Article. Products are identified by using entrance door hardware designations as follows:

t res

NORTHWESTERN UNIVERSITY

PROJECT NAME _____

JOB # _____

FOR: _____

ISSUED: 03/29/2017

B. Weld in concealed locations to greatest extent possible to minimize distortion or discoloration of finish. Remove weld spatter and welding oxides from exposed surfaces by descaling or grinding.

C. Fabricate components that, when assembled, have the following characteristics:

1. Profiles that are sharp, straight, and free of defects or deformations.
2. Accurately fitted joints with ends coped or mitered.
3. Physical and thermal isolation of glazing from framing members.
4. Accommodate thermal expansion and contraction.

NORTHWESTERN UNIVERSITY
PROJECT NAME _____
JOB # _____

FOR: _____
ISSUED: 03/29/2017

topcoat. Prepare, pretreat, and apply coating to exposed metal surfaces to comply with coating and resin manufacturers' written instructions.

1. Color and Gloss: <Insert color and gloss>.

2.10 SOURCE QUALITY CONTROL

- A. Structural Sealant: Perform quality-control procedures complying with ASTM C 1401 recommendations including, but not limited to, assembly material qualification procedures, sealant testing, and assembly fabrication reviews and checks.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine areas, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance.

NORTHWESTERN UNIVERSITY

PROJECT NAME _____

JOB # _____

FOR: _____

ISSUED: 03/29/2017

- E. Install glazing as specified in Section 088000 "Glazing."
- F. Install weatherseal sealant according to Section 079200 "Joint Sealants" and according to sealant manufacturer's written instructions to produce weatherproof joints. Install joint filler behind sealant as recommended by sealant manufacturer.
- G. Entrance Doors: Install doors to produce smooth operation and tight fit at contact points.
 - 1. Exterior Doors: Install to produce weathertight enclosure and tight fit at weather stripping.
 - 2. Field-Installed Entrance Door Hardware: Install sur0 Td [(E)2.4(nx)-8.2()6.3(0 Td [(E)2.4(nx)-8.2(s)-88B1

NORTHWESTERN UNIVERSITY

PROJECT NAME _____

JOB # _____

FOR: _____

ISSUED: 03/29/2017

- D. Aluminum-framed entrances and storefronts will be considered defective if they do not pass tests and inspections.
- E. Prepare test and inspection reports.

3.6 ENTRANCE DOOR HARDWARE SETS

END OF SECTION 08 4113

NORTHWESTERN UNIVERSITY
PROJECT NAME _____
JOB # _____

FOR: _____
ISSUED: 03/29/2017

THIS PAGE IS INTENTIONALLY BLANK